

# KRISHNASAMY

College of

## **ENGINEERING & TECHNOLOGY**

Approved by AICTE & Affiliated to Anna University

### Consultancy – Mata Amritanandamayi Math Dated: 10.03.2022



### Mata Amritanandamayi Math

Amrita Vidyalayam, ECR Road, Kirumampakkam, Puducherry, 6074

10.02, 2022

Poincipal
Kaishnasway Egineering College
Kaddalose

Reguest De are newly Constructing Amosta Vidya Byens School in Kisuman pekkan at possychery distoict for this we have to measure the strength of the Conact Cabe. In also test is required for this so we tindly request you to approve the abertal in your College ab. The Caber were laid on 2/02/2022. 1:1:2 disgo mix mas after Seven days Size (0:15 x 0:15 x 0:15)

**Inward Letter** 

Visada. P.

882591442

RECEIPT

Receipt No. FC21/03279 Date : 10/03/2022

Mano : AMRITHA VIOYALAVAN, ECR RD Class :

Particulars Amount

TESTING CUBES 450.

Total 450.

Amount is Words : Rupees Four Hundred and Fifty Only

Cashier

Bill receipt for testing





College of

# **ENGINEERING & TECHNOLOGY**

Approved by AICTE & Affiliated to Anna University



### KRISHNASAMY COLLEGE OF ENGINEERING & TECHNOLOGY

(Affiliated to Anna University) CUDDALORE - 607 109

#### DEPARTMENT OF CIVIL ENGINEERING

### TEST REPORT

Receipt No:FC21/03279

DATE:10.03.2022

Issued to:

The incharge,

Amirtha Vidyalayam,

ECR Road,

Kirumambakkam, Puducherry – 607 402

Properties of Cement Concrete Cube for 7 days

S. No	Mark on the Specimen	Grade of Concrete	Date of Casting	Date of Testing	Weight of Cube (kg)	Ultimate Load (kN)	Compressive Strength (N/mm²)
1	02.03.2022	M25	02.03.2022	08.03.2022	8.650	290	12.88
2	02.03.2022	M25	02.03.2022	08.03.2022	8.850	220	9.77
3	02.03.2022	M25	02.03.2022	08.03.2022	8.590	250	11.11

P. Oui.

(Er.P.DINESH KUMAR)
ASSISTANT PROFESSOR OF CIVIL ENGG.

fined of the Department Civil Engg.

Testing report for the given sample